Complete Electrical Solutions Co., Ltd.

Bangkok : Sathorn Prime Tower, Unit No.07 10th Floor, 26 Naradhiwas-Rajanagarindra Road, Yannawa, Sathorn, Bangkok 10120
Phuket : 34/23 M.1, Sakdidej Rd, T.Wichit, A.Muang, Phuket 83000
www.ces-asia.com

Quotation No. : **Q_KNX_037R3-26PA_Stepwise_Romsai Restaurant**

Project : **Romsai Restaurant**

Date : **2 April 2026**

Attn : **คุณรัตนพล**

From : **K.Phiromrat A.** **Tel : 065 542 6592** **phiromrat@ces-asia.com**

Subject : **Quotation KNX Merten Lighting Control system**

Item	Description	Amount	Quantity	Total amount
1	ROMSAI RESTAURANT & LIFT LOBBY & ROMSAI WC	342,636.00	1	342,636.00
Total				**342,636.00**
Vat 7%				23,984.52
Grand Total Price				**366,620.52**

Remark :

1. Control แบบ On/Off (จำนวนโหลดต้องไม่เกิน 16A ต่อ 1 วงจร) , Phase dimming (จำนวนโหลดต้องไม่เกิน 1A ต่อ 1 วงจร) และ 1-10V dimming (จำนวนโหลดต้องไม่เกิน 10A ต่อ 1 วงจร)
2. ราคาที่นำเสนอจะมีในส่วน Interior (ROMSAI Restaurant) เท่านั้น
3. ราคาที่นำเสนอนี้อุปกรณ์ทุกตัวจะต้องเชื่อมต่อถึงกัน(จะต้องเป็นสาย KNX เท่านั้น)
4. ราคานี้ นำเสนอตามเอกสารของ Bo Steiber (ROMSAI Restaurant) เท่านั้น
5. ราคาที่นำเสนอนี้ ไม่ได้เชื่อมต่อกับระบบ lighting control เดิมและไม่ได้เชื่อมต่อกับระบบอื่นๆ
6. จำนวนสวิทช์อ้างอิงตามจำนวนของเอกสาร Bo Steiber (ROMSAI Restaurant)
7. ราคาที่นำเสนอนี้ ไม่รวมงานติดตั้งและการเดินสายWiring ระหว่างชั้นและอุปกรณ์ต่างๆที่เชื่อมต่อกับระบบอื่นๆ

Remark : This price in Thai Baht and excluding VAT.

Delivery : 60-120 days after received purchase order and deposit.
Delivery to Bangkok Area

Validity : 15 days from the date of quotation.

Payment : The payment shall be paid as below:
- Credit 60 Days.

Cancellation Order CES will not refund deposit in case of customer refuse to receive goods by the time goods arrival.

Scope of work

1. Providing all material according to this quotation.
2. Providing the service and work according to this quotation.
3. Providing drawing of control panel.
4. Providing the engineer to advise the installation for one time and total service 4 times.

The customer have to provide the qualify and responsible person for this training. Notice 7 days in advance.

Complete Electrical Solutions Co., Ltd.

Bangkok : Sathorn Prime Tower, Unit No.07 10th Floor, 26 Naradhiwas-Rajanagarindra Road, Yannawa, Sathorn, Bangkok 10120
Phuket : 34/23 M.1, Sakdidej Rd, T.Wichit, A.Muang, Phuket 83000
www.ces-asia.com

Quotation No. : **Q_KNX_037R3-26PA_Stepwise_Romsai Restaurant**

Project : **Romsai Restaurant**

Date : **2 April 2026**

5. Warranty condition :

5.1 Warranty period is 12 months after testing but not later than 15 months after the delivery date of material.

5.2 Warranty is under the normal usage and right condition and the damaged shall be caused by factory defect.

5.3 Warranty is not cover when using inappropriate or wrong working condition or any other's modify and change.

5.4 Any damage under the above condition, we will repair and change the part without any charge according to the below condition

5.4.1 Customer has to present the warranty document every against the service request

5.4.2 This warranty is not cover the standard equipment such as power outlet, switch, lighting and accessory, cable which not under the warranty.

5.4.3 Any damaged caused by wrong operation, accident or disaster such as fire, flood, earthquake are not under the warranty.

As per the above condition, customer has to response for the part, repair and service.

5.5 Company reserve the right to charge the service and part for the repair in case that not under the warranty condition.

The work that customer has to provide the material and installation for below :

1. Provide all cable and wiring work including signal cable EIB cable C-Bus
2. All cable wiring from load center to lighting control and to all load of lighting and other including all cable termination work.
3. The mounting of lighting control panel and the switch including cable termination work
4. Provide other equipment such as lighting fixture, switch, power outlet etc.
5. Provide and install the junction box for all switch and other equipment

In case of using any LED lamp and/or electronic driver and/or power supply with our supplied product, the compatibility

and performance of light and control may be varied depend on case by case and are not under our responsibility.

The warranty of product for that LED circuit is not valid in this case.

My best regards,

Phiromrat Arumugam

(Sales Manager)

Complete Electrical Solutions Co.,Ltd.

Bangkok : Sathorn Prime Tower, Unit No.07 10th Floor, 26 Naradhiwas-Rajanagarindra Road, Yannawa, Sathorn, Bangkok 10120
Phuket : 34/23 M.1, Sakdidej Rd, T.Wichit, A.Muang, Phuket 83000
www.ces-asia.com

Quotation : Q_KNX_037R3-26PA_Stepwise_Romsai Restaurant

Project : Romsai Restaurant

Date : 2 April 2026

Subject : Quotation KNX Merten Lighting Control system

Item	Code	Description	Brand	Price list (Baht/unit)	Qty (Pcs)	Discount	Total amount (Baht)
		ROMSAI RESTAURANT & LIFT LOBBY & ROMSAI WC					
1	MTN6710-0102S	Dimming actuator, SpaceLogic KNX, Universal, 230V, white	Schneider	21,000.00	2	50%	21,000.00
2	MTN6810-0102	SpaceLogic KNX Universal Dimming, Extension 2 channel	Schneider	12,500.00	3	50%	18,750.00
3	MTN646991	Control unit 0-10 V REG-K/3-gang with manual mode, light grey	Schneider	15,500.00	17	50%	131,750.00
4	MTN6705-0008S	Blind/switch actuator, SpaceLogic KNX, master, 8 channels, 250V, 16A, white	Schneider	18,500.00	1	50%	9,250.00
5	MTN6513-1202	Power supply, Spacelogic KNX, REG-K/640 mA	Schneider	27,500.00	1	50%	13,750.00
6	DRL-24V75W1AZ	LYTE DIN Rail Power Supply, 24Vdc/3.125A, 75W	Delta	1,060.00	1	40%	636.00
7	LSS100200	Schneider Electric logic controller, SpaceLogic KNX, spaceLYnk, 50 users, grey	Schneider	86,000.00	1	50%	43,000.00
8	C2E616201_WE_C1 4 Key	KNX push button, Cuadro H, 15mA, 21-30 VDC, 4 gang, white	Schneider	9,000.00	1	50%	4,500.00
9	C2E616401_WE_C1 8 Key	KNX push button, Cuadro H, 15mA, 21-30 VDC, 8 gang, white	Schneider	10,000.00	3	50%	15,000.00
10	CP-KNX	Control Panel	Local	33,500.00	1	NET	33,500.00
11		Testing & Commisioning	Local	51,500.00	1	NET	51,500.00
Total							**342,636.00**